



DIRECTORATE GENERAL OF HIGHWAYS  
 MINISTRY OF PUBLIC WORKS  
 REPUBLIC OF INDONESIA



AUSTRALIAN  
 INTERNATIONAL DEVELOPMENT  
 ASSISTANCE BUREAU

# SISTEM MANAJEMEN SYSTEM



# BRIDGE CONSTRUCTION TECHNIQUES MANUAL

JANUARY 1993



SNOWY MOUNTAINS ENGINEERING CORPORATION LIMITED

SMC - Kinhill Joint Venture



KINHILL ENGINEERS PTY LTD

TERKENDALI

# TABLE OF CONTENTS

1. INTRODUCTION	1-1
1.1 SCOPE OF MANUAL	1-1
1.2 SUMMARY OF STANDARD BRIDGE TYPES	1-1
1.2.1 General	1-1
1.2.2 Foundations	1-1
1.2.3 Substructures	1-2
1.2.4 Superstructures	1-2
1.3 SELECTION OF APPROPRIATE CONSTRUCTION METHOD	1-6
2. PILING TECHNIQUES	1
2.1 GENERAL	2-1
2.1.1 Transport	2-1
2.1.2 Preparation for piling installation	2-1
2.1.3 Setting out of Piles	2-1
2.1.4 Handling and Pitching	2-2
2.1.5 Test Loading	2-2
2.1.6 Capacity of Piles	2-4
2.2 CONCRETE PILES	2-5
2.2.1 General	2-5
2.2.2 Manufacture	2-5
2.2.3 Precast Prestressed Concrete Piles	2-6
2.2.4 Handling and Storage	2-6
2.2.5 Splicing and Extending	2-7
2.3 STEEL PILES	2-13
2.3.1 General	2-13
2.3.2 Fabrication	2-13
2.3.3 Splicing	2-14
2.3.4 Concrete in Piles	2-15
2.4 DRIVEN PILES	2-15
2.4.1 General	2-15
2.4.2 Pitching	2-15
2.4.3 Driving Procedure	2-16
2.4.4 Driving	2-17
2.4.5 Test Piles	2-21
2.5 BORED PILES	2-22
2.5.1 General	2-22
2.5.2 Boring	2-22
2.5.3 Excavation	2-22
2.5.4 Enlarging of bases	2-23
2.5.5 Rock Socket	2-23
3. CAISSON INSTALLATION	3-1
3.1 GENERAL	3-1
3.2 CONCRETE - CAST IN SITU	3-1
3.2.1 Setting Out	3-1
3.2.2 Preliminary Excavation	3-1
3.2.3 Casting of Concrete Segments	3-1
3.2.4 Excavation	3-2
3.2.5 Dewatering	3-3
3.2.6 Adding concrete segments	3-3

<b>4. CONCRETE PRODUCTION</b>	
4.1 GENERAL	4-1
4.2 MIX DESIGN	4-1
4.2.1 General	4-1
4.2.2 Design Method	4-1
4.2.3 Trial Mixes	4-25
4.2.4 Control of Mix During Contract	4-26
4.3 BATCH METHODS	4-27
4.3.1 General	4-27
4.3.2 Handling of Materials	4-27
4.3.3 Volume Batching	4-27
4.3.4 Weigh Batching	4-29
4.4 MIX METHODS	4-30
4.4.1 Mix Records	4-30
4.4.2 Ready Mixed Concrete	4-33
4.4.3 Site Mixing	4-35
4.4.4 Transport of Concrete	4-35
4.4.5 Retempering of Concrete	4-37
4.5 CONTROL OF CONCRETE PRODUCTION	4-38
4.5.1 General	4-38
4.5.2 Consistency of Concrete	4-38
<b>5. CONCRETE CONSTRUCTION</b>	
5.1 GENERAL	5-1
5.2 FORMWORK AND FALSEWORK	5-1
5.2.1 General	5-1
5.2.2 Formwork	5-1
5.2.3 Joints	5-10
5.2.4 Falsework	5-11
5.3 REINFORCEMENT	5-12
5.3.1 General	5-12
5.3.2 Materials	5-12
5.3.3 Delivery of Steel	5-12
5.3.4 Stacking on Site	5-12
5.3.5 Bending on Site	5-13
5.3.6 Cleaning Prior to Placing in Forms	5-13
5.3.7 Bond, Anchorage and Splicing	5-13
5.3.8 Cover to Reinforcement	5-14
5.3.9 Positioning and Tying	5-15
5.3.10 Tack Welding of Reinforcement	5-16
5.4 PLACEMENT OF CONCRETE	5-16
5.4.1 General	5-16
5.4.2 Placement methods	5-16
5.4.3 Placing concrete under water	5-21
5.4.4 Compaction of Concrete	5-21
5.4.5 Surface Finish of Concrete	5-23
5.4.6 Curing of Concrete	5-26
5.4.7 Quality of Concrete	5-29
5.4.8 Joints	5-30

5.5	PRESTRESSED CONCRETE	5-36
5.5.1	General	5-36
5.5.2	Ducting for Prestressing Tendons	5-36
5.5.3	Tendons and Anchorages	5-37
5.5.4	Stressing	5-38
5.5.5	Safety Precautions	5-44
5.5.6	Grouting	5-44
5.5.7	Handling and Storage of Precast Prestressed Girders and Deck Units	5-46
5.5.8	Practical Details	5-47
5.6	DEFECTIVE CONCRETE	5-52
5.6.1	General	5-52
5.6.2	Repair methods	5-53
6.	STEEL SUPERSTRUCTURE ERECTION TECHNIQUES	
6.1	GENERAL	6-1
6.2	AUSTRALIAN TRUSS	6-1
6.2.1	Permanent Truss	6-1
6.2.3	Semi-Permanent Truss	6-30
6.3	AUSTRALIAN GIRDER	6-35
6.3.1	General	6-35
6.3.2	Components	6-38
6.3.3	Erection Methods	6-39
6.3.4	General Problems	6-40
6.4	DUTCH TRUSS (HOLLANDIA KLOOS)	6-43
6.4.1	General	6-43
6.4.2	Components	6-45
6.4.3	Erection Methods	6-45
6.4.4	General Problems	6-53
6.5	AUSTRIAN TRUSS	6-54
6.5.1	Permanent Truss	6-54
6.5.2	Semi-Permanent Truss	6-61
6.6	COMPARISON OF AUSTRALIAN, DUTCH AND AUSTRIAN PERMANENT TRUSS	6-64
6.7	TEMPORARY BRIDGING (TRANSPANEL AND MABEY COMPACT)	6-65
6.7.1	General	6-65
6.7.2	Australian Transpanel Bridge	6-65
6.7.3	Mabey Johnson Compact Bailey	6-70
7.	BEARINGS AND JOINTS	
7.1	GENERAL	7-1
7.2	BEARINGS	7-1
7.3	JOINTS	7-2
8.	WATERWAY AND EMBANKMENT PROTECTION	
8.1	GENERAL	8-1
8.2	GABIONS	8-1
8.3	STONE PITCHING	8-2
8.4	SHEET PILING	8-3

9. ROAD APPROACHES

9.1	GENERAL	9-1
9.2	MATERIALS	9-2
9.3	COMPACTION	9-2
9.4	BITUMINOUS SURFACING	9-2

LIST OF REFERENCES

SALINAN